

Bill of Quantities · SYN-2026-001

BILL OF QUANTITIES (Preamble + selected items)

Preamble Note 1. Rates entered in this BoQ shall be deemed to include all labour, materials, plant, supervision, profits, overheads, and all other costs reasonably incurred or to be incurred by the Contractor in execution of the items, whether expressly mentioned or not.

Preamble Note 2. Items shall be measured net as built. No allowance shall be made for waste, breakage, or shrinkage unless specifically stated.

Preamble Note 7. Items in this BoQ have been priced on the basis of project completion within 6 months of the date of the LoA, as required by Special Conditions Clause 5.5 reporting cycle. Any extension of this period shall entitle the Contractor to a price-adjustment claim.

Item 1.01 Excavation in all types of soil including disposal within 500 m. Unit: cum. Quantity: 12,500.

Item 2.01 Plain cement concrete grade M15, including formwork. Unit: cum. Quantity: 850.

Item 2.02 Reinforced cement concrete grade M30, including formwork, reinforcement extra. Unit: cum. Quantity: 2,400.

Item 2.03 High-yield-strength deformed reinforcement bars (Fe 500D) including cutting, bending, placing. Unit: tonne. Quantity: 320.

Item 4.01 Bituminous concrete wearing course, 50 mm thick. Unit: sqm. Quantity: 18,000.